


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRANCIS M. RAYMOND
Farm- Unruh No. 1

SEC. 25 T. 20 R. 15W
NE NE SE

Total Depth. 3640'
Comm. 5-8-59 Comp. 5-19-59
Shot or Treated.
Contractor. Raymond Drlg.
Issued. 9-19-59

County Barton
KANSAS



CASING:
8 5/8" 871' cem w/450 sx.
5 1/2" 3640' cem w/100 sx.

Elevation. 1912' DF

Production. 45 BOPD

Figures Indicate Bottom of Formations.

surface hole	65
shale & shells	293
Dakota sand	388
shale, red bed, lime shells	475
shale, shells & iron pyrite	660
shale & iron pyrite	853
Anhydrite (Surface Hole)	871
Anhydrite	873
red bed	980
shale & shells	1400
shale	1685
lime & shale	1800
shale with lime	1925
lime with shale	2010
lime	2115
lime & shale	2138
shale & lime	2980
lime with shale	3018
lime	3062
lime & shale	3201
shale & lime	3230
lime & shale	3358
lime	3464
lime with shale	3550
chert	3562
shale, lime & chert	3603
sand	3605
shale	3616
shale w/lime	3628
dolomite	3640 RTD
Total Depth	

TOPS:
Anhydrite 853
Heebner 3208
Toronto 3224
Douglas 3242
Brown Lime 3308
Lansing 3326
Conglomerate Chert 3550
Simpson 3602
Arbuckle 3628