


Company- S. R. LAUCK OIL, INC.
Farm- Dorman No. 4

SEC. 27 T. 20 R. 15W
NW NE SE

Total Depth. 3673
Comm. 3-17-66 Comp. 3-25-66
Shot or Treated.
Contractor. D. R. Lauck Oil
Issued. 5-21-66

County Barton

KANSAS



Elevation. 1937' KB

Production. Dry

CASING:

8 5/8" O 907' w/469 sx.

Figures Indicate Bottom of Formations.

surface clay	10
sand	50
shale	332
sand	439
shale & red bed	903½
Anhydrite	932
shale & shells	1720
shale & lime	3080
lime	3240
lime & shale	3360
lime	3673 RTD
Total Depth	

SAMPLE TOPS

Anhydrite (driller)	904
Heebner	3247
Brown Lime	3345
Lansing	3355
Conglomerate	3619
Arbuckle	3662

DST #1 (W) 3610-65, opn 1 hr w/strong blow 1 hr. Gas do sfc. 8 min., too small to measure. Rec. 250' gassy mud. ISIP 1077#/30 min. FSIP 1022#/30 min. IFP 69#, FFP 93#.

DST #2 (W) Misrun 3663-68', opn 1 hr w/fair blow. Test was a misrun dur to tool being plugged. Rec. 1680' gas in pipe. No pressures.

DST #2 (W) 3663-68' opn 1 hr w/strong blow 1 hr. Gas to surface 31 min, too small to measure. Rec. 60' OCM, 120' very muddy oil with estimated 3 to 4 gallons free oil & 1 gallon water. ISIP 1140#/30 min, FSIP 1124#/30 min., IFP 39# FFP 47#.

DST #3 (W) 3665-73' opn 1 hr w/good blow 1 hr. Rec. 3350' gas in pipe & 480' fluid; 60' thin watery mud, 60' mud-cut oil, 120' very muddy oil with a show of water, 60' oily water, 180' water. ISIP 1149#/30 min., FSIP 1149#/30 min. IFP 47#, FFP 147#.