


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

AMERADA PETROLEUM CORPORATION.
Geo. T. Bowyer No. 1.

SEC. 12 T. 20 R. 16W.
CSL SE SW

Total Depth. 3844 P.S. 3833
Comm. 6-23-41 Comp. 7-12-41
Shot or Treated.
Contractor. Crow Drilling Co.
Issued. 9-27-41

County Pawnee



CASING.

85/8" 684' cemented.
5 1/2" 3844' cemented.

Elevation.

Figures Indicate Bottom of Formations

Production. Pot. 14,423 B.
Indicated capacity.

surface clay	20
sdv gravel	56
shells	125
shale	352
shale and shells	489
sand	635
red rock	958
shale and shells	1091
anhydrite	1133
shale and shells	1345
broken lime	1375
shale	1395
shale and shells	1496
shale	1558
salt and shale	1780
lime	1795
broken lime	1840
lime	1878
lime and shale	1925
lime	2055
cherty lime	2080
lime	2243
cherty lime	2252
lime	2308
shale	2334
broken lime	2363
lime	2391
shale	2405
lime	2437
shale	2461
broken lime	2494
lime	2503
lime and shale	2582
shale	2601
lime	2629
lime and shale	2670
lime	2680
shale	2720
lime	2740
shale	2765
lime	2772

shale	2822
lime	2839
shale	2885
broken lime	2943
lime	3036
broken lime	3066
shale	3077
lime	3144
broken lime	3195
cherty lime	3203
broken lime	3235
lime	3539
lime hard	3570
lime very soft	3585
lime	3757
Arbucklo	3844

Total Depth.

Plugged back 3833

Tops.	Anhydrite	1091
	Kansas City	3491
	Arbucklo	3757

508 bbls oil no water, flowed 10 hrs.
indicated capacity 14,423 bbls.