


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

AMERADA PETROLEUM CORP.
Geo. T. Bowyer No. 2

SEC. 12 T. 20 R. 16W.
CNL SE SW

Total Depth. 3825
Comm. 7-22-41 Comp. 8-7-41
Shot or Treated.
Contractor. Crow Drilling Co.
Issued. 9-27-41

County Pawnee



CASING.

85/8" 696' cemented.
5 1/2" 3825' cemented.

Elevation.

Production. Pot. 12,377B.
Indicated Capacity.

Figures Indicate Bottom of Formations.

surface clay	17
shale and shells	137
shale	148
sand	165
shale and shells	430
sand and shells	525
red rock	680
sand	690
shale and shells	700
shale and sand	781
red bed	945
shale and shells	1089
anhydrite	1122
shale and shells	1552
salt and shale	1812
lime	1820
shale and lime	1865
lime	1890
shale	1910
shale and lime	2017
shale	2045
lime cherty	2109
broken lime	2175
lime	2267
lime and shale	2925
lime	2990
lime and shale	3176
lime	3403
lime and shale	3428
lime	3558
lime soft	3578
lime	3587
chert and lime	3602
lime	3608
chert and lime	3632
lime	3747
Arbucklo dolomite	3825
Total Depth.	

drilled cement to 3824

374 bbls flowed 11 hours, Potential
indicated capacity 12,377 bbls. -
Adjusted to maximum well of 3000 B.
Geological Tops:
Kansas City 3477
Arbuckle 3747

Perf. 5 1/2" csg w/Lane Wells
from 3824-3821 w/11 shots -
hole filled up 2400' in 1 hr
10 minutes. In 2 hrs filled
up 3000'
Acidized w/300 Gals. Acid 8-14-41