

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

MID CONTINENT PETROLEUM CORP.  
G.P. Smith No. 1.


SEC. 13 T. 20 R. 16W.  
NWc SE

Total Depth. 3811  
Comm. 10-23-37 Comp. 12-10-37  
Shot or Treated.  
Contractor. Mac & Stauffer  
Issued. 2-5-38

County Pawnee.

CASING.

15 $\frac{1}{2}$ " 20'9"  
103/4 728'  
7" 3753'



Elevation. 2080

Production. Pot. 284 B.

Figures Indicate Bottom of Formations.

soil	4	lime	<del>3720</del>
clay	35	shale	3735
shale	38	conglomerate	3745
sand	50	shale	3751
shale	400	conglomerate	3759
shale shells	445	shale	3762
shale	470	lime siliceous	3811
sand	500		
red rock	920	Total Depth.	
shale	1010		
lime	1040	show oil 3764	
red rock	1083	Good show oil 3770	
anhydrite	1115	good show oil 3809	
lime	1180		
shale	1250		
lime broken	1292	Gas 1,570,000 3762-70	
shale brown	1570	Inc. gas 37,750,000 3810-11	
salt	1655		
shale	1790		
lime	1830		
shale	1870		
lime	2012		
shale	2053		
lime	2170		
shale	2205		
lime	3330		
lime broken	3385		

3762  
2080  
-----  
-1682