


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.  
 N.A.Belt No. 3.

SEC.13 T.20 R.16W  
 CE $\frac{1}{2}$  NW SW  
 1980' N SL 990' E WL SW $\frac{1}{4}$

Total Depth. 3867' PB 3863'  
 Comm. 12-28-40 Comp. 1-25-41  
 Shot or Treated.  
 Contractor.  
 Issued. 3-29-41 Rotary O-3867

County. Pawnee



CASING:  
 8 5/8" 657'5"  
 5 1/2" 3866'4"

Elevation.

Production. Pot.2332 B.Allowed

Figures Indicate Bottom of Formations.

cellar	10
shale - clay	102
sticky clay	170
sand	190
shale - sand	284
shale blue sticky	366
sand	425
shale blue	480
sand & shells hrd	642
red beds	1110
anhydrite	1140
shale & shells	1630
salt	1670
salt & shell	1700
shale & shells	3280
lime	3500
shale	3538
lime	3625
lime brkn	3645
lime	3793
shale	3801
dolomite	3867
Total Depth.	

Plugged back 3863

Top Arbuckle 3801

35 BPH Natural -- Pot.Test BPH  
 Method -- 2915 Indicated  
 capacity  
 20% Wtr -- Pot.Allowed 2332  
 Average Gas/Oil ratio 1500