

Texon

SIMPSON OIL CO. & TEXON OIL & LAND CO.
Matilda Nelson No. 1.

SEC. 14 T. 20 R. 16W
NEc SE

Total Depth. 3806'


County. Pawnee

Comm. 5-15-39 Comp. 6-10-39

Shot or Treated. 500 & 1000 Gals.

Contractor. Simpson & Noble, Inc.

Issued. 7-22-39 Rotary w/cable
tool completion



CASING:

10 3/4" 700'
6" 3801'

Elevation.

Production. Pot. 354 B.

Figures Indicate Bottom of Formations.

clay & sand	223
red bed & shells	342
shale & sholls	515
sand	605
red bod	1055
anhydrito	1075
lime & sholls	1120
shalo & sholls	1951
lime brkn	2700
shale	2702
shale & lime	2833
shale & shells	2925
shale & lime	2940
lime & shale brks	3010
lime brkn	3158
lime & shale brks	3188
lime brkn	3433
shale & lime shells	3475
lime hrd(K.C.)	3489
lime brkn	3501
lime	3556
lime oolitic	3580
limo hd & chert	3616
lime brkn	3742
shalo & limo	3767
limo brkn & shalo	3774
limo Arbucklo	3806
Total Depth.	

(reworked dolomite & green
shalo 3777-3778
dolomite porous & gas 3784
dolomite, hrd strk & green
shalo & saturation in spots 3787)

500 Gals. Acid 6-13-39
1000 Gals. Acid 6-16-39

Top of Arbucklo 3774