


Plotted for
18-20-5W

REPUBLIC NATURAL GAS CO.
Swanson No. 3

SEC. 18 T. 20 R. 5W.
CW $\frac{1}{2}$ NE SW

Total Depth. 3349'
Comm. 5-21-40 Comp. 6-15-40
Shot or Treated. No
Contractor. E.K. Carey.
Issued. 7-6-40

County McPherson.



CASING.	Rotary	3310
	Cable	3349
85/8"	117'	
5 1/2"	3307'	

Elevation.

Production. Pot. 6800B.

Figures Indicate Bottom of Formations.

shale and shells	107
red bed & shale	125
red bed & shells	270
shale blue and shells	450
shale and shells	800
salt shale and shells	850
shale and shells	1070
lime and shale	1333
sdv broken lime	1370
shale and lime	1680
shale and shells	1900
shale	2100
shale and shells	2170
shale and lime	2275
lime	2407
shale	2415
lime	2453
lime and shale	2510
lime	2528
lime and shale	2625
shale and shells	2665
broken lime	2678
shale	2738
shale and shells	2755
lime	2804
lime and shale	2836
lime	3069
shale	3115
shale and lime	3197
shale	3258
shale and lime	3307
chat	3349
Total Depth.	