

13-20-2W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: GLICKMAN OIL CO.
Farm: L. Koehn No. 1

SEC. 13 T. 20 R. 2W
NW NW NE

Total Depth. 2986
Comm. 9-27-54 Comp. 10-7-54
Shot or Treated.
Contractor. J. A. Melland
Issued. 11-13-54

County McPherson
KANSAS



CASING:

Elevation. 1537

8 5/8 @ 152' w/ 125 sx cmt.
5 1/2 @ 2984' w/ 75 sx cmt.

Production Flow 24 BO,
700,000 Gas

Figures Indicate Bottom of Formations.

shale & sand	40
shale, sand & shells	152
shale & shells	295
lime	490
lime & shale	645
sand & shale	720
lime	735
shale & lime	930
lime	975
shale & lime	1125
shale	1620
lime	1740
shale & lime	1780
lime	1880
lime & shale	2080
shale	2290
lime	2425
shale & lime	2925
chat	2934
cherty lime	2960
chat	2986
Total Depth	

SCOUT TOPS:
Kansas City 2294
Mississippi 2925

DST #1: 2925-34, open 1 hr. gas to
surf. 4 min. rec. 500' free oil, IFP
55#, FFP 135#, BHP 455# - 11 hrs. 1 min.

DST #2: 2960-86, open 30 min. good
blow, decreased. rec. 60' OCM, 270'
muddy oil, 870' SW, BHP 622# - 19 hrs.