

13-20-2W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- GLICKMAN OIL CO.  
Farm- L. Koehn No. 3

SEC. 13 T. 20 R. 2W  
NW SW NE

Total Depth. 2971'  
Comm. 12-8-54 Comp. 12-16-54  
Shot or Treated.  
Contractor. J. A. Melland  
Issued. 1-29-55

County McPherson  
KANSAS



CASING:  
8 5/8" 157'  
5 1/2" 2967' cem w/100 sx

Elevation. 1512' RB

Production. 45 BO

Figures indicate Bottom of Formations.

surface soil, shale & shells	157
shale & lime	350
lime	505
shale & shells	575
lime & shale	660
shale & sand	720
lime & shale	740
shale & lime	925
lime & shale	990
shale	1075
shale & shells	1385
shale	1460
lime, shells & shale	1560
shale	1620
lime & shale	1690
shale & shells	1745
lime & shale	1890
shale & lime	1905
lime	1990
lime & shale	2080
sand & shale	2220
lime & shale	2245
shale & lime	2355
lime & shale	2430
shale & lime	2505
lime & shale	2615
shale, lime & shells	2705
shale & lime	2915
shale	2926
cherty lime	2943
Mississippi lime	2965
lime	2968
Mississippi lime	2971
Total Depth	

#1 2926-2943', open 40 min., gas to surface in 2 min., flowed oil in 35 min., SI 20 min, 510' of clean oil, FT-110#, FT-275#, BHP-520# - 12 hrs. & 47 min.

#2 2943-2965', open 1 hr., Rec. 40' of drilling mud. 9 hrs. & 19 min.

Tops: Scout  
Mississippi 2929

DRILL STEM TESTS: