

4-20-2W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ARNOLD AKERSON
Farm- Stucky No. 3

SEC. 4 T. 20 R. 2W
 NW SE NW

Total Depth. 3392'
Comm. 5-14-63 Comp. 5-23-63
Shot or Treated.
Contractor. Blackstone Drlg.
Issued. 6-5-65

County McPherson
 KANSAS



CASING:

Elevation. 1533' RB

3 5/8" 178' cem w/ 100 sx
5 1/2" 3392' cem w/ 140 sx

Production. 25 BOPD PLUS W

Figures Indicate Bottom of Formations.

COMPLETE DRILLER LOG NOT AVAILABLE

LIMESTONE no shows 2321-2329
chert, show free oil,
light spotted stain,
evidence of gas, ~~slight shows~~ of
free oil, faint odor in wet
sample. 2951-2966
Dolomite show free oil
and spotted stain, faint to
fair odor 2991-2993

TOPS: LOG

Lansing	2313
Mississippian	2951
Kinderhook	3187'
Maquoketa Dolomite	3391

DST # 12952-2968 Op 1 hr, gas to
surface in 28 min., rec. 90' of
slightly oil and gas cut mud and 120'
of salt water, flow pressures 27 to
108 psi, bottom hole pressures 485 and
467 psi. in 20 min.

No Electric run