


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- JONES, SHELburnE & FARMER
Farm- Uhland No. 1

SEC. 3 T. 20 R. 20
SE SE SE

Total Depth. 4676'
Comm. 8-23-57 Comp. 9-10-57
Shot or Treated.
Contractor. Jones, Shelburne & Farmer, Inc.
Issued. 11-9-57

County Pawnee
KANSAS



CASING:

8 5/8" 280' cem w/175 sx

Elevation. 2225 DF

Production. Dry

Figures indicate Bottom of Formations.

Surface clay	30
Shale & shells	380
Shale & redbed	770
Sand	850
Shale, sand & red bed	1275
Shale & red bed	1390
Anhydrite	1425
Shale, shells & red bed	1665
Shale & red bed	1785
Shale & shells	2200
Lime	2235
Shale & lime	3550
Lime	4090
Lime & shale	4150
Lime	4225
Lime & shale	4295
Lime	4330
Lime & shale	4365
Lime (cherty)	4412
Lime	4435
Lime sand	4470
Lime	4535
Lime & chert	4570
Lime	4635
Lime arbuckle	4676
Total Depth	

TOPS:

Anhydrite	1390
Heebner	3704
Toronto	3724
Lansing	3755
Base Kansas City	4086
Cherokee Shale	4185
Cherokee Sand	4248
Mississippi	4317
Mississippi Lime	4405 (Scout)
Kinderhook	4460
Viola	4496
Simpson	4599
Arbuckle	4611