

State **Kansas** County **Barton**

Company **Rock Island Oil & Ref. Co.** Well No. **1**

Farm **Deckert**

Survey _____

Block No. _____ Sec. **20** Twp. **20 S** Range **15 W**

Co-Ord. _____ Elev. **2039**

W/2 W/2 SE/4

Gas Purchaser:
Ks. Western (?)

BTU 999 (Means Lab.)

Ash Creek Pool

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
2/5/62		Spud - 8-5/8" @ 793'
	3368	Heebner
	3399	Douglas
	3459	Brown Lime
	3471	Lansing
	3701	Bs. K.C.
	3773	Arbuckle (-1734)
	D.S.F. #1	- 3778-90' - Op 1 hr., GTS
		in 1 1/2", Ga. 1,710 Mcf - 5"

688708

Date	Depth	
		2,310 Mcf - 10"
		Stab. 2,420 Mcf - 20"
		BHP 870-866/30", FP 321-323#
		D.S.T. #2 - 3790-3815' - Op 1 hr., GTS
2/16/62		in 1 1/2", Ga. 1,930 Mcf - 5"
		2,250 Mcf - 10"
		Stab. 2,310 Mcf 20"
		BHP (30") 912-891#, FP 311-311
	3875	R.T.D. 3" @ 3874'
2/19		Perf. 3776-3800
2/20		B/D - SI press. 850#
		B/D 10:00 a.m. Ga. 3,310 Mcfg ^{wet}
		11:00 a.m. Ga. 3,400 Mcfg ^{wet}
		12:noon Ga. 3,500 Mcfg ^{dry}
		1:00 p.m. Ga. 3,500 Mcfg ^{dry}
		2:00 p.m. Ga. 3,500 Mcfg ^{dry}
		BTU 999 Means Lab.)
3/8/62		Ks.-Nebr. Gas Test:
		530# - - 1,500 Mcfg
		485# - - 1,990 Mcfg
		330# - - 2,300 Mcfg
		275# - - 2,400 Mcfg
		Making 21 gal. dist. - 7 hrs.