

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- PICKRELL DRILLING CO.

Farm- Moore

No. 2

SEC. 7

T. 20

R. 21W

C NW NW

Total Depth. 4377' (4370)

Comm. 3-18-64 Comp. 3-29-64


Shot or Treated.

Contractor. Company Tools

Issued. 6-13-64

County Ness

KANSAS



Elevation. 2231' RB

Production. 112 BOPD, NW

CASING:

8 5/8" 255' cem w/175 sx.

5 1/2" 4358' cem w/75 sx.

Figures Indicate Bottom of Formations.

clay	25
post rock	105
shale & shells	255
shale	295
shale & shells	615
redbeds	755
Blaine	780
sand	1125
shale & shells	1450
Anhydrite	1485
shale & shells	2165
lime & shale	2530
lime	2785
lime & shale	3618
sdv lime & shale	3650
lime & shale	3755
lime	4080
lime & shale	4355
Mississippian	4370 RTD
Mississippian ?	4377
Total Depth	

TOPS: SAMPLE

Anhydrite	1448
Heebner	3720 (3722)
Lansing	3768 (3770)
Ft. Scott	4273 (4275)
Mississippi	4348 (4350)