

10-20-21W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL
Farm- McJunkin "A" No. 3

SEC. 10 T. 20 R. 21W
150' W/ CNE SW
660'S & 1874' E of W/4 corner

Total Depth. 4409PB4403
Comm. 3-28-65 Comp. 4-6-65
Shot or Treated. 12 shots 4396-4403', Mississippian, 250 Gals. acid
Contractor. Peel Bros.
Issued. 6-19-65

County Ness KANSAS



CASING:
8 5/8" 511' 275 sx.
4 1/2" 4408' 100 sx.

Elevation. 2235' KB

Production. 58 BO & 48 BW 24hrs.

Figures Indicate Bottom of Formations.

clay & rock	60
shale & shell	280
shale	515
shale & shells	895
sand	1110
shale & red beds	1453
anhydrite	1485
shale & shell	2200
lime & shale	2380
lime	2735
lime & shale	2990
shale & lime	3325
lime & shale	3755
lime	4399
chert	4409
BTD	

ELECTRIC LOG TOPS:

Anhydrite	1453
Heebner	3752
Toronto	3772
Lansing	3798
Base Kansas City	4134
Fort Scott	4305
Cherokee	4324
Conglomerate	4366
Mississippi	4393
LTD	4411