

18-20-23W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY R. V. LEHNER


SEC. 18 T. 20 R. 23W
 LOC. C SW SW

FARM Lehner NO. B-1

TOTAL DEPTH 4410'
 COMM. 7-9-68 COMP. 7-18-68
 SHOT OR TREATED
 CONTRACTOR Strat Drilling
 ISSUED 10-5-68

COUNTY Ness

KANSAS



CASING

20	10	
15	8	5/8" 289' cem w/ 150 sx
12	6	
13	5	

ELEVATION 2312' KB

PRODUCTION DRY/MISS

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay	0	40
Rock Part, Clay, Sand & Shale	40	311
Shale & Shells	311	915
Shells, Red Bed & Shale	915	1538
Anhydrite	1538	1575
Red Bed & Shale	1575	1786
Shale & Lime	1786	3909
Lime	3909	4384
Cherty Lime	4384	4410

Ran 288.38' of new 8-5/8" surface casing; set and cemented at 288.28' with 150 sacks of regular cement and 2% gel. Plug down at 12:30 A. M. July 10, 1968.

Total Depth 4410'

TOPS: SMP	
Anhydrite	1538
Heebner	3738
Lansing	3793
Pawnee	4226
Fort Scott	4302
Mississippi	4404
RTD	4410

D. & A.

Plugged hole as follows: Plugged at 720' with 70 sacks of cement; plugged at 270' with 20 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 8:30 A. M. July 13, 1968.

(STATE OF KANSAS)

