

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

14-20-24W

Company- KEWANEE OIL CO.

Farm- Petersilie

No. 3

SEC. 14 T. 20 R. 24W

SE SE SW

330' fr SL, 330' fr EL of
SW/4

County Ness

KANSAS

Total Depth. 4475' PB 4404.5'

Comm. 10-22-58

Comp. 11-4-58

Shot or Treated.

Contractor. Graham-Michaelis Drlg. & K & A Drlg.

Issued. 2-14-59

CASING:

8 5/8" 522.15' cem w/350 sx.

5 1/2" 4473.06' cem w/100 sx.

2 3/8" 4400.23' (O. D. Tubing)

Elevation. 2312' CM

Production. IP 36.94 BO, NW in
24 hrs.

Figures Indicate Bottom of Formations.

surface	0
surface clay & sand	85
clay & shale	160
shale	270
sand	315
shale & shells	665
clay, red bed & shale	1380
shale & red bed	1500
shale & shells	1720
shale & lime	2510
lime	2709
lime & shale	3979
lime	4349
cherty conglomerate	4385
cherty lime	4413
Mississippi lime	4475
Total Depth	
Plugged back to	4404.5'

TOPS: C.M. MEAS.	SAMPLE	SCHLUMBERGER
Heebner	3710	3708
Toronto	3724	3726
Lansing-Kansas City	3781	3786
Base Kansas City	4112	4119
Marmaton	4130	4131
Cherokee	4273	4278
Conglomerate	4353	4358
Mississippi	4382	4387

Treating Record: Acidized w/6750 gallons
Sand-oil treated w/15,000 GHO & 15,000#
sand preceded by 1000 gal acid.

Perforating Record: Perforated from 4388'
to 4410' w/58 holes. (4399-4400 - 4 holes,
4392-4400' - 33 holes and 4388-4392 w/21 holes.