

MARSHALL W.

Form 113 50M 11-48-45997-D

State Kansas County Barton (I)

Sec. 24 Twp. 20 Rng. 12 W Elev. 1813'

Company York State

Well No. 1 Name Scheufler

Location SW SW SE

Feet from lines: N. S. E. W.

Spud 2-3-49 Completed 3-30-49  
8" 266

T. D. 3358' Casing 5" 3342'

Comp. Perf.

Pay Arb. 3342-58

I. P. Phy. 110 BOPD, tr. wtr.

Choke T. P. C. P.

G. O. R. Grvty. 39.3

DATE	REMARKS
<u>3-30-49</u>	<u>Heeb. 2969, Tor. 2987, Brn. Lm. 3095, Lane. 3110, Arb. 3341, Poor por. tr. live stn. 3114-18, Poor por. res. stn. 3128-32 314 man.</u>

DATE	REMARKS
	sptd. live stn. 3178-83. Fr. por.
	poor sptd. stn. to sat. 3189-
	99. Sli. por. poor to fr. sptd.
	stn. 3202-10. Poor por. poor
	sptd. stn. 3239-43. Poor por.
	poor sptd. stn. 3254-58. Sli.
	to fr. por. sptd. stn. fnt. odor
	3274-87. Gr. delo. sli. por. sptd.
	stn. fr. odor 3341-44. Schl.
	RTD 3344. DF CO TH. B/5 BO in
	2½ hr. DD 3347. B/1½ BOPH 2
	hr. FU 600' fluid 6 hr. Swb.
	15 BO to bottom. 500 A. 500#
	broke to 250#. Swb. 79 BW +
	20 BO 9 hr. DD 3355. No inc.
	FU 150' oil. DD 3358. FU
	250' oil. Swb. 60 BO 12hr. Swb.
	23 BO 6 hr. P. 97 BO 9 hr.
	P. 138 BO + 7 BW 24 hr.
	COMPLETE
	969769