

BRYANT SE

Form 113 50M 4-49-47450-D

State Kansas County Barton

Sec. 26 Twp. 20 Rng. 12W Elev. 1826

Company Phillips Petroleum

Well No. 1 Name Schrepel

Location S/2 NW SE

Feet from lines: N. S. E. W.

Spud 7-15-49 Completed 10-5-49

T. D. 3452 Casing 5" 3382

Comp. Perf.

Pay

I. P. D & A

Choke T. P. C. P.

G. O. R. Grvty.

**COMPLETION**

DATE	REMARKS
10-5-49	Heeb. 3008, Tor. 3022, BrL. 3184, LKc. 3148, Arb. 3381;
BYLE	HEWYKES

DATE	REMARKS
	3026-34, Fr. Xpor., tr. sptd. stn.
	3152-57, Fr. Xpor. tr. sptd. to
	even stn., slit. odor. 3164-70,
	Fr. to fr. col. to slty col.
	por., tr. sptd. stn., sptd.
	show free oil, fr. odor.
	3237-61, Fr. to fr. col. to
	X por. NS. 3274-84, Fr.
	collicastic por. tr. dark resi.
	stn., tr. heavy dark free oil,
	vy. slit. odor. 3112-24 pr.
	to fr. colli-castic por., NS.
	3383-TD, poor to fr. por.,
	fr. sat., fr. odor, sli. show
	free oil. 3028-35, fr. por.
	poss. oil, 3150-56, fr. por.
	poss. oil., 3162-68, pr. por, prob
	oil. 3183-85 & 3188-90, Fr.
	por. poss. oil, 3233-48, fr.
	por. prob. wtr. 3271-79, fr. por.
	prob. wtr. 3110-21, fr. por.
	prob. wtr. 3381-TD, fr. por.,
	prob. oil. Recommended Perfor-
	ations: 3026-35, 3150-57,
	3162-70, 3183-90.
	5" casing set 3382, cable tool
	rigged up, plug drilled bailed
	1 GPH, hole deepened to 3389
	tested 3 1/2 GPH. Hole cored
	from 3389-3403 & bailed 22 1/2 BOPH
	ET/1989

DATE	REMARKS 686143
	grav. 37.9 in 4 hr., Acidized 500 gals tested 1/2 BO & 3/4 acid wtr 5 hr. cored 3403-3407 tstd 21 gals oil, 3 gal. in 1 hr. First wtr encountered @ 3405-07. Hole was cored and drilled deeper to 3452 TD only sli. inc. in wtr. was noted. Badly caving hole was encountered @ 3431. Well PB to 3419 & formation acidized with 500 gals. & tstd. 15 GO / 69 GWH 2 hr. Well PB to 3400 & perforated in LKc with 23 / 3183-90 & bld. 2 1/2 GWH. PB to 3347 & perfs. were acidized w/500 gals. & tstd. 2 1/2 BW / 2 BO/20 hr. PB to 3174 & csg. perf. LKc w/32 / from 3162-70, SSG. Perfs. were acidized w/500 gals. & tstd. 9 GO / 26 CW/3hr. Formation was reacidized with 2000 gals. and bld. 11 GO / 19 1/2 CW/2. Grav. 36.7 PB to 3158 & perf. W/29 / 3150-57 in LKc., NS. Acidized w/500 gals. tstd. 17 GO / 57 CW 3 hr. PB 3128 W/36 / from 3026-35 in Tor. Acid 500 gals/tstd.

