


15-101-22147

7-20s-28w



DRILL STEM TEST REPORT

Prepared For: **TRANS PACIFIC CORPORATION**

100 S MAIN SUITE #200
WICHITA KS 67202

ATTN: MACK ARMSTRONG

7-20S-28W LANE

BUSH"A"#1-7

Start Date: 2008.12.04 @ 19:55:00

End Date: 2008.12.05 @ 03:27:00

Job Ticket #: 16675 DST #: 1

Superior Testers Enterprises LLC
PO Box 138 Great Bend KS 67530
1-800-792-6902

Printed: 2008.12.07 @ 21:50:54

TRANS PACIFIC CORPORATION


BUSH"A"#1-7

7-20S-28W LANE

DST # 1

JOHNSON

2008.12.04



DRILL STEM TEST REPORT

TRANS PACIFIC CORPORATION

100 S MAIN SUITE #200
WICHITA KS 67202

ATTN: MACK ARMSTRONG

BUSH"A" #1-7

7-20S-28W LANE

Job Ticket: 16675

DST#: 1

Test Start: 2008.12.04 @ 19:55:00

GENERAL INFORMATION:

Formation: **JOHNSON**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 21:49:30
Time Test Ended: 03:27:00

Test Type: Conventional Bottom Hole (Initial)
Tester: JARED SCHECK
Unit No: 3320 -220- GB

Interval: **4578.00 ft (KB) To 4642.00 ft (KB) (TVD)**
Total Depth: 4642.00 ft (KB) (TVD)
Hole Diameter: 6.88 inches Hole Condition: Fair

Reference Elevations: 2789.00 ft (KB)
2780.00 ft (CF)
KB to GR/CF: 9.00 ft


Serial #: 8524

Inside

Press@RunDepth: 64.11 psia @ 4637.00 ft (KB)
Start Date: 2008.12.04 End Date: 2008.12.05
Start Time: 19:56:00 End Time: 03:27:00

Capacity: 5000.00 psia
Last Calib.: 2008.12.05
Time On Btm: 2008.12.04 @ 21:48:30
Time Off Btm: 2008.12.05 @ 01:20:30

TEST COMMENT: 30/INITIAL OPEN:WEAK BLOW BUILT 1 1/2 INCH INTO BUCKET 20 MIN STAYED STEADY THROUGHOUT
60/INITIAL SHUT IN:NO BLOW BACK
45/FINAL OPEN:VERY WEAK SURFACE BLOW DID NOT BUILD STAYED STEADY THROUGHOUT
75/FINAL SHUT IN:NO BLOW BACK



PRESSURE SUMMARY


Time (Min.)	Pressure (psia)	Temp (deg F)	Annotation
0	2385.92	121.61	Initial Hydro-static
1	60.38	121.08	Open To Flow (1)
31	62.54	122.50	Shut-In(1)
91	1222.38	125.81	End Shut-In(1)
91	62.74	125.44	Open To Flow (2)
136	64.11	127.89	Shut-In(2)
211	1168.84	130.16	End Shut-In(2)
212	2275.82	130.47	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
10.00	MUD 100%	0.14

Gas Rates

Choke (inches)	Pressure (psia)	Gas Rate (Mcf/d)



DRILL STEM TEST REPORT

TOOL DIAGRAM

TRANS PACIFIC CORPORATION

BUSH"A"#1-7

100 S MAIN SUITE #200
WICHITA KS 67202

7-20S-28W LANE

Job Ticket: 16675

DST#: 1

ATTN: MACK ARMSTRONG

Test Start: 2008.12.04 @ 19:55:00


Tool Information

Drill Pipe:	Length: 4555.00 ft	Diameter: 3.80 inches	Volume: 63.89 bbl	Tool Weight:	10000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose:	75000.00 lb
		Total Volume:	63.89 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	6.00 ft			String Weight: Initial	55000.00 lb
Depth to Top Packer:	4578.00 ft			Final	55000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	64.00 ft				
Tool Length:	93.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4550.00	
Shut-In Tool	5.00			4555.00	
Hydraulic Tool	5.00			4560.00	
Jars	6.00			4566.00	
Safety Joint	2.00			4568.00	
Packer	5.00			4573.00	29.00 Bottom Of Top Packer
Packer	5.00			4578.00	
Change Over Sub	0.75			4578.75	
Perforations	28.00			4606.75	
DRILL PIPE	29.50			4636.25	
Change Over Sub	0.75			4637.00	
Recorder	0.00	8524	Inside	4637.00	
Recorder	0.00		Outside	4637.00	
Bullnose	5.00			4642.00	64.00 Bottom Packers & Anchor

Total Tool Length: 93.00



DRILL STEM TEST REPORT

FLUID SUMMARY

TRANS PACIFIC CORPORATION

BUSH"A"#1-7

100 S MAIN SUITE #200
WICHITA KS 67202

7-20S-28W LANE

Job Ticket: 16675

DST#: 1

ATTN: MACK ARMSTRONG

Test Start: 2008.12.04 @ 19:55:00

Mud and Cushion Information

Mud Type: Gel Chem

Mud Weight: 9.00 lb/gal

Viscosity: 51.00 sec/qt

Water Loss: 9.99 in³

Resistivity: ohm.m

Salinity: 3200.00 ppm

Filter Cake: 1.00 inches

Cushion Type:

Cushion Length:

Cushion Volume:

Gas Cushion Type:

Gas Cushion Pressure:

ft

bbl

psia

Oil API:

Water Salinity:

deg API

ppm

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
10.00	MUD 100%	0.140

Total Length: 10.00 ft Total Volume: 0.140 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

DST Test Number: 1


7-20S-28W LANE

TRANS PACIFIC CORPORATION

Inside

Serial #: 8524

Pressure vs. Time



Printed: 2008.12.07 @ 21:50:55

Ref. No: 16675

Superior Testers Enterprises LLC