

27-20-3W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company SLICK-PRYOR-LOCKHART  
Farm Stucky No. 3.

SEC. 27 T. 20 R 3 W  
CWL SW $\frac{1}{4}$

DEEPENING RECORD

Total Depth. 3463 $\frac{1}{2}$ '  
Comm. 10-16-33 Comp. 11-14-33  
Shot or Treated. Shot 40 Qts.  
Contractor.  
Issued. 12-7-46

County. McPherson  
KANSAS



CASING:  
12 $\frac{1}{2}$ " 176'  
8 $\frac{1}{4}$ " 3330'

Elevation. \_\_\_\_\_

Production. Swb 462 B.16 hrs

Figures Indicate Bottom of Formations.

no log	176	11-17-33 swabbing
brkn	371	from 1 to 6 P. M. ave.
shale	487	35 BPH
shale lime shells	620	from 6 to 11 P.M. ave.
lime brkn	735	31 BPH
shale	800	11-18-33 swbd 239 B.in
lime	840	7 hrs.
shale & shells	882	11-19-33 swbd 159 B.
lime	905	5 hrs.
shale shells	1005	
lime shells	1129	<u>DEEPENING RECORD:</u>
shale shells	1650	Aylward Prod. Co.
lime	1710	Comm. 8-18-45
shale shells	1872	Comp. 6-21-46
shale	1895	Prod. 350 B, Est.
lime	1950	
shale shells	1980	Cort r - Aylward Prod.Co.
lime	2110	
shale	2310	
lime	2605	Wilcox sand 3419-38
lime hd	2637	shale 3440
lime	2695	sand hd 3450
shale	2705	shale sdy green 3460
lime	2728	Arbuckle lime 3463 $\frac{1}{2}$
shale	2750	Total Depth.
lime	2770	
shale	2795	Hole filled up 2000'
lime	2855	w/oil in 20 minutes
shale shells	2894	from 3461-63 $\frac{1}{2}$ , no wtr
shale	2985	
shale shells	3011	
Top chat 3011		
chat hd	3024	
chat	3070	
lime	3105	
shale shells	3120	
shale	3324	
lime	3330	
lime Viola	3383	
lime	3391	
Wilcox sand	3419	
very lgt sh oil	3380	
Total Depth	3419	

Swabbing -  
1st hr 28 B,  
2nd hr 18 B,  
3rd hr 15 B,  
4th hr 15 B.  
5th hr 15 B.  
6th hr 15 $\frac{1}{2}$  B.

Top Wilcox 3391 Steel Line