

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas.

33-20-3W

SINCLAIR PRAIRIE OIL COMPANY
 McCurdy No. 7

SEC. 33 T 20 R. 3W
 NW NE SE

MAR 10 1934

County. McPherson.


Total Depth. 3327

Comm. 11-22-33 Comp. 2-7-34

Shot or Treated. 1st shot.-20 qts 3312-26 2nd shot.-20 qts 3290-3304

Contractor.

Issued. 3-10-34



CASING

Rotary

15 1/2" 209 8 1/4" 2965'

Elevation.

Production. 619 B. Pot.

Figures Indicate Bottom of Formations.

cellar	12	shale	3072
clay	30	shale	3250
sand and clay shells & sand	90	lime	3263
gravel sand and lime shells	160	lime	3284
shale and lime shells	209	shale green	3288
shale	390	bailed down below chat and waiting	
shale and shells	690	for gas to show up.	
shale	820	sand	3316
shale and lime	900	show gas and oil 3294-3304	
shale and shells	1000	sand	3324
shale and lime	1100	shale green	3327
shale	1765	T.D.	
broken lime	1890		
shale and lime	1960	300' fluid 3327 before shot.	
lime	2040	Swabbed 74 bbls., 22 hours. before	
shale	2200	shot.	
broken lime	2235		
shale	2304		
lime	2330	After shot Swabbed 25 bbls 1st hour	
shale	2360	Swabbed 15 bbls per hr.	
lime	2510		
lime	2535	Swabbed 55 bbls 3 hours.	
sand	2585		
lime	2670		
shale	2685		
lime	2700		
shale	2720		
lime and shale	2785		
lime	2800		
shale	2880		
shale and shells	2923		
shale	2963		
lime	2978		
chat	2990		
Top of chat 2963			
chat	3035		
shale and shells	3040		