

APR 14 1934

SINCLAIR PRAIRIE OIL CO.
McCurdy No. 8

SEC. 33 T. 20 R. 3 W.
SW NE SE

Total Depth, 3296.
Comm. 2-7-34 Comp. 3-28-34.
Shot or Treated. 20 qts 3272-92 2nd 20 qts 3262-82
Contractor.
Issued. 4-14-34

County. McPherson.



CASING.

15 1/2" 193' 65/8" 3215

Elevation.

Figures Indicate Bottom of Formations. Production. Potential
511 bbls.,

shale	40
sand	50
sand and gravel	80
shale and shells	195
no log	200
shale sand and shells	390
broken lime and gyp	480
gyp and lime	550
lime and shale	755
broken lime and shale	860
shale and lime shells	1020
no log	1110
lime	1150
shale	1360
red rock	1380
lime	1475
shale and lime	1545
shale	1630
shale and shells	1790
lime	1800
shale	1836
shale and lime	1895
broken lime and shale	1948
lime	2070
shale	2095
shale and lime	2125
shale	2295
lime	2325
lime and shale	2350
lime	2385
lime	2475
shale	2484
lime	2580
sdv lime	2596
lime	2735
shale	2835
broken lime and shale	2878
shale	2950
shale and shells	2955

Top chat 2948 samples.

chat 2975

chat and shale 2988
Top Kinderhook around 2988
shale and lime 3005
shale 3194

lime	3255
dolomite brown	3256
shale green	3260
sand	3291
shale green	3296

corrected total depth.

Final corrections.

Top of Viola (base shale)	3194
Top of white lime	3224
Base Viola	3255
Brown dolomite	3255-56
shale green	3256-60
Wilcox sand	3260-91
shale green	3291-3296TD.

Swabbed 10 bbls per hr.