

33-20-3W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BRUNSON PRODUCTION & EXPLORATION, INC.
Farm- Stucky "E" No. 1

SEC. 33 T. 20 R. 3W
SW NW SE

Total Depth. 4355
Comm. 9-29-56 Comp. 10-18-56
Shot or Treated.
Contractor. Brunson Prod. & Expl. Inc.
Issued. 11-17-56

County McPherson
KANSAS



CASING:

8 5/8" 252'
5 1/2" 3165'

Elevation. 1458 RB

Production. Dry

Figures indicate Bottom of Formations.

surface soil	15
sand	120
shale, lime	190
shale	440
lime	460
shale, lime	1122
shale, shells	1660
lime, shale	3085
lime, chert	3095
chert, lime, shale	3137
lime	3162
shale, lime	3233
shale	3395
chert, lime	3515
lime	3540
sand	3541
sand, pyrite	3597
sand, shale	3638
lime, shale	3650
lime	3678
lime, sand	3729
sand, lime	3760
lime, sand, chert	3798
lime, chert	4077
lime, sand, chert	4346
lime, sand	4352
sand, pyrite	4355
Total Depth	

Tops:	
Brown lime	2408
Lansing	2456
Miss. Chert	3051
Lime	3139
Kinderhook	3178
Maquoketa	3481
Viola	3505
Simpson shale	3537
Simpson sand	3540
Basal Sand	3588
Arbuckle	3637
Cambrian sand	4324
Granite Wash	4355