

KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
Union National Bank Bldg, Wichita, Kansas

GYSEY OIL COMPANY  
C. L. Stucky No. 3

SEC. 33 T. 20 R. 3W  
SW corner SE NE


DEEPENING RECORD

Total Depth. 3422'  
Comm. 11-6-33 Comp. 12-12-33  
Shot or Treated.  
Contractor.  
Issued. 4-10-48

County. McPherson

CASING.

15 $\frac{1}{2}$ " 183' 65/8" 3287 $\frac{1}{2}$ '  
8 $\frac{1}{2}$ " 2988' 3" 3343



Figures Indicate Bottom of Formations. Production. 546 B.  
24 hours

1458 net

|                                                                       |                    |          | <u>HISTORY</u>                           |
|-----------------------------------------------------------------------|--------------------|----------|------------------------------------------|
| soil                                                                  | 35                 |          |                                          |
| sand                                                                  | 90                 |          |                                          |
| shale                                                                 | 183                | 12-12-33 | Swab 41 $\frac{1}{2}$ B. Oil 7 hours     |
| shells                                                                | 196                |          |                                          |
| shale                                                                 | 225                | 12-13-33 | Shot 40 qts 3361 $\frac{1}{2}$ to 3384   |
| lime                                                                  | 230                |          |                                          |
| shale and shells                                                      | 765                | 12-19-33 | Swab 12 B.O.P.H.R for 9 hours            |
| shale and lime shells                                                 | 855                |          |                                          |
| shale and lime                                                        | 1065               | 12-21-33 | Swab 197 B. C. in 16 hours               |
| shale and shells                                                      | 1215               |          |                                          |
| sdv shale                                                             | 1565               | 12-24-33 | Swab 216 B. in 20 hour                   |
| shale                                                                 | 1542               |          |                                          |
| broken lime                                                           | 1618               | 12-27-33 | Swab 187 B. in 21 hours                  |
| broken lime and shale                                                 | 1766               |          |                                          |
| lime and shale                                                        | 1825               | 12-29-33 | Swab 205 B. oil 19 hours                 |
| lime                                                                  | 1903               |          |                                          |
| lime and shale                                                        | 1975               | 12-30-33 | Swab 194 B. oil in 18 hours              |
| lime                                                                  | 2135               |          |                                          |
| broken lime                                                           | 2150               | 1-2-34   | Shot 60 qts 3357 to 3384                 |
| shale                                                                 | 2275               |          |                                          |
| lime                                                                  | 2355               | 1-7-34   | Swab 118 B. in 9 hours                   |
| shale and lime                                                        | 2342               |          |                                          |
| lime                                                                  | 2345               | 1-9-34   | Swab 107 B. in 7 hours                   |
| shale and shells                                                      | 2395               |          |                                          |
| lime                                                                  | 2492               | 1-10-34  | Swab 140 B. in 11 hours                  |
| shale and lime shells                                                 | 2532               |          |                                          |
| lime                                                                  | 2692               | 1-11-34  | Swab 221 B. in 16 hours                  |
| shale                                                                 | 2890               |          |                                          |
| shale                                                                 | 2982               | 1-15-34  | Swab 118 B. in 11 hours                  |
| <u>SAMPLE LOG</u>                                                     |                    |          |                                          |
| chat 2982-                                                            | 3038               |          | Run Tubing and Rods                      |
| Top of Chat 2982                                                      |                    |          |                                          |
| lime                                                                  | 3067               | 1-22-34  | Pump 372 B. O and 13 B. Wtr 16 hours     |
| shale                                                                 | 3280 $\frac{1}{2}$ |          |                                          |
| dolomite argillaceous                                                 | 3310               | 1-23-34. | Pump 353 B. Oil and no wtr 20 hours      |
| lime white xyn                                                        | 3340               |          |                                          |
| shale green                                                           | 3355               | 1-25-34  | Potential Test.                          |
| sand                                                                  | 3384               |          | Pump 546 B. Oil in 12 B. Water in 24 Hr. |
| Pay 3355-3376                                                         |                    |          |                                          |
| sdv shale green                                                       | 3390               |          |                                          |
| TD.                                                                   |                    |          |                                          |
| Standardized 3287 $\frac{1}{2}$                                       |                    |          |                                          |
| Hole filled 600' with oil from 3355 to 3376 in 15 $\frac{1}{2}$ hours |                    |          | (OVER)                                   |

Gulf Oil Corp.

#3 C.L.Stucky

SW SE NE of Sec.33-20-3W

Deepening Record:

Comm. 5-27-47 Comp. 6-1-47

Production -

Before P. 6 oil, 50 wtr

After Pot. 120 oil,  
67 wtr 6-10-47

Acidized w/1000 Gals.6-3-47

lime? 3390-3422

Total Depth.

Top of Arbuckle 3416

5 $\frac{1}{2}$ " OD 162' (5 jts.)

set at 3255 to 3417

Perf. 3346-3391