


GYPSY OIL COMPANY.
Emma Stucky No. 3

SEC. 33 T. 20 R. 3 W.
SE NW SE

Total Depth. 3399½
Comm. 2-16-34 Comp. 4-6-34
Shot or Treated.
Contractor.
Issued. 4-28-34

County. McPherson.

APR 28 1934



CASING.

15½" 171' 65/8" 3365'

Elevation.

Production. Potential

Figures Indicate Bottom of Formations. 582 B. 24 hours.

sand	150	shale	2280
shale	165	shy shale	2310
gyp	171	shale	2315
shale and shells	242	shale and lime shells	2395
shale and shells	340	lime	2420
shale and shells	485	lime	2500
broken lime	575	shy lime	2511
shale	610	broken lime	2520
broken lime	634	lime	2560
shale	650	shale	2570
gyp and lime	695	lime	2684
broken lime	735	shale and lime shells	2710
shale	745	lime	2720
broken lime	780	shale and shells	2732
shale and red rock	810	shale	2759
lime and shale	835	lime and shale	2775
broken lime	860	shale	2795
lime	872	shale and shells	2815
broken lime	915	shale	2947
shale	931	lime	2950
broken lime	940	SAMPLE LOG.	
shale	950	shale red	2950- 2965
broken lime	995	chert, pink yellow, white	2978
shale	1020	grey crystalline limestone	3000
no log	1080	shale grey	3246
lime	1090	cherty dolomite	3261
broken lime	1115	Standardized at 3249½	
shale	1137	white crystalline limestone	3293
broken lime	1165	dolomite sand and green	
shale	1220	dolomitic shale	3296
shale & lime shells	1315	show oil 3296.	
shale and lime	1430	sand and green shale	3317
shale	1445	Water from 3313-3317 Bailed 12 BWPH for 11 hours	
lime	1475	and had bailed water to within 50' of bottom of hole	
shale	1482	at end of 11 hour test.	
shale and lime-		shale green and little sand	3373
shells	1530	dolomite	3375
shale and lime	1570	Filled 40' with oil in 5 hours at 3375	
shale and lime-		dolomite	3383
shells	1634	Filled 2100' with oil from 3377-3383 overnight	
shale	1682	and swabbed 5 BO.PH after being swabbed down.	
broken lime	1692	dolomite	3395.
broken lime	1712	Increase in oil 3390-3393. BEST PAY	
lime	1900	dolomite	3399½ T.D.
broken lime	1920	no increase in oil.	
shale	1940	4-6-34 Swab 205 b oil in 5 hours.	
broken lime	1945	4-11-34 Pump 128 B.Oil and no water in 5 hours.	
shale and lime-	1975	4-13-34. Pump 582 bbls oil and no water for a	
shells	2005	24 hour Potential test.	
shale	2145		
sand	2155	NOTE- All of the oil in this test is being produced	
shale	2165	from the Siliceous lime. No oil was found in the	
sand	2175	Wilcox sand Zone. and no typical body of Wilcox	
shale	2190	sand was present.	
sand	2200		