

UNION NATIONAL BANK BLDG WICHITA KANSAS.


Location NW cor SW.

Sec..34 T.. 20 R..3W..

Casing Record

10" Farm- H. M. Kinney. No. 4
 20" 8 1/2" 3025 Company- Gypsy Oil Co.
 15 1/2" 183 65/8" 3408' Contr.-
 12 1/2" 53/16" Comm.- 7/31/30. Comp.- 9/3/30.
 Total Depth 3458' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

County- McPherson



Elevation 1476

Figures Indicate Bottom of Formations.

Initial Production

Date Issued. 11/1/1930.

985 bbls.

Formation	Depth
soil sand shale	120
shale sand	160
shale	175
lime	210
sand & shale	310
shale & shells	475
lime	551
shale lime shells	750
brkn lime	775
shale shells	1505
brkn lime shale	1660
shale lime shells	1760
brkn lime shale	1865
shale	1890
brkn lime	1930
shale	2005
brkn lime	2060
shale & shells	2100
brkn lime	2150
shale	2270
sdv shale	2330
shale	2370
lime	2410
sdv lime	2465
brkn lime	2500
sdv lime	2530
shale	2565
lime	2710
shale	2730
sand	2740
shale	2770
lime shale	3010
shale	3025
chat	3130
shale	3370
brkn lime	3380
Viola lime	3415
lime	3433
shale	3439
Wilcox sand	3448
Sand	3458 TD

3130
 3025
 105

3380
 3130
 250

Following tops by Geol. Price.

Mississippi	3025-3160
Kinderhook shale	3160-3378
Galina chert & dolo	3378-3403
Viola	3403-3433
Simpson green shale	3433 to 3439
Wilcox sand	3439 to 3458

Had green shale break in the Wilcox sand
 from 3448 to 3450'

Wilcox sand 3439 to 3458
 Shale break 3448 to 3450'