

90008

7-175W  
MAP NO.

SEC. 34 TWP. 20S RGE. 35W

STATE Kans COUNTY Wichita LOC. C NW SW

OPERATOR Amarillo Oil Co. FT. FROM LINE


WELL NO. 1 FARM NAME Grace T. Weesner FT. FROM LINE

COL. WC-7 miles NW of Nunn\* ELEV. 3175 GR 3180 DF 3183 KB

FR. 5/10/62 SPUD. 5/12/62 COMP. 7/24/62

CONT. Garvey Drlg. Rig #12 /GEOL.

| NAME PRODUCING INTERVAL | COMPLETION RECORD<br>FROM - TO | PERF. W/HOLES | TREATMENT RECORD |
|-------------------------|--------------------------------|---------------|------------------|
| a Marm                  | 4523-63                        | 40            | 1000 A           |
| b                       |                                |               |                  |
| c                       |                                |               |                  |
| d State Pot: Pump       |                                |               |                  |



a I. P. OIL/DIST. 30 BO WTR. NW GAS M.C.F.P.D. CHK. HRS. 24

b " " " " " "

c " " " " " "

d

D &amp; A ( )

SIP# FI TP # FI CP# SIBHP

GOR. GR. 31.70 PBTD 4732 TD 5007

| SIZE          | DEPTH | CASING - CEMENT RECORD<br>W/SAX. | SIZE | DEPTH | W/SAX. |
|---------------|-------|----------------------------------|------|-------|--------|
| 8 5/8" @ 478  |       | 350                              |      |       |        |
| 4 1/2" @ 4732 |       | 155                              |      |       |        |

OPERATOR Amarillo Oil Co. WELL NO. 1 Grace T. Weesner ELEV. 3183 KB

| SAMPLE TOPS                                                      | DEPTH | SUB SEA | ELEC. TOPS            | DEPTH | SUB SEA |
|------------------------------------------------------------------|-------|---------|-----------------------|-------|---------|
| *North, Marm Oil) KB Tops & Datums                               |       |         |                       |       |         |
| RTD (St Lou) 5076                                                | -1893 |         | Herr                  | 2696  | + 487   |
| DST #1 (Marm) 4521-62, Op                                        |       |         | Winf                  | 2782  | + 401   |
| 1 hr., F to GB, Rec 15'                                          |       |         | Hb                    | 3971  | - 788   |
| HOCM & 90' oil & 30'                                             |       |         | No Lans Picked        |       |         |
| mdy oil, IBHP 1185#/, 30", Marm                                  |       |         |                       | 4509  | -1326   |
| IFP 21#, FFP 43#, FBHP                                           |       |         | Morr                  | 4892  | -1709   |
| 1141#/, 30".                                                     |       |         | Unconformity          | 4963  | -1780   |
| DST #2 (Marm) 4611-44, Op                                        |       |         | St. Lou               | 5000  | -1817   |
| 30", WB/died, R 15' m,                                           |       |         | St Lou (Poro) 5034-52 |       | -1851   |
| IBHP 1208#/, 30", IFP                                            |       |         | LTD                   | 5077  | -1894   |
| 10#, FFP 10#, FBHP 1029#/, 30".                                  |       |         |                       |       |         |
| RTD 5076. Log. 4 1/2" @ 4732 w/155 sx, PBTD 4732. 8/4523-25      |       |         |                       |       |         |
| (Marm) 8/4534-36 (Marm) 8/4540-42 (Marm) 8/4557-59 (Marm)        |       |         |                       |       |         |
| 8/4561-63 (Marm) 1000 acid, Swb 83 BLW of 95 total ld,           |       |         |                       |       |         |
| F level 4100', Swb 5 BFPH (90% oil) 3100' OB, CP 10#,            |       |         |                       |       |         |
| Swb 13 BO, 2 1/2 hrs., Swb 34 1/2 BO/4 hrs., Swb 63 BO & 63 BLW, |       |         |                       |       |         |
| 250' OB. Log - S-J. POP. Pump 7 BO/24 hrs., P 22 BO/24           |       |         |                       |       |         |
| hrs, Pump 4 BOPH/NT, Pump 18 BO/24 hrs., P 15-3/4 BO/24 hrs.     |       |         |                       |       |         |
| State P: P 30 BOPD/NW, Gr 31.70, Marm 4523-63. COMPLETED         |       |         |                       |       |         |

LIBERAL ELECTRIC LOG TOPS

3182 KB

Winfield 2794 (+388)  
Heebner 3970 (-808)  
Toronto 3982 (-820)  
Lansing 4014 (-852)  
Marmton 4509 (-1347)  $\phi$  IP 30 BO/24 hrs.  
Morrow 4892 (-1730)  
Miss 4962 (-1800)  
St. Louis (Opr) 5000 (-1838)  
TD 5076