

3-20-4W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. WHITE & ELLIS, et al
Farm- Schindler No. 1

SEC. 3 T. 20 R. 4W
SE SE NE

Total Depth. 3863
Comm. 5-5-57 Comp. 5-20-57
Shot or Treated.
Contractor. White & Ellis Drilling, Inc.
Issued. 7-27-57

County McPherson
KANSAS



CASING:
8 5/8 563' w/ 470 sx cmt.

Elevation. 1483 RB

Production. Dry

Figures Indicate Bottom of Formations.

soil	9
sand	165
shale	420
sand	500
shale & gravel	516
salt	532
shale & salt	556
shale & lime	562
lime	563
lime & sand streaks	650
red rock	660
lime	740
shale & lime	810
shale	830
lime w/ shale streaks	990
shale	1020
lime	1060
shale & lime	1260
lime w/ shale streaks	1385
shale	1630
shale & shells	1710
shale w/ lime streaks	1940
shale & lime	2000
sticky shale	2145
lime	2294
shale & lime streaks	2335
sandy shale	2369
sand	2453
shale	2546
lime	2660
shale	2672
lime & shale	2801
lime	2920
shale & lime	3137
shale & shells	3188
lime	3447
shale	3739
lime	3768
dolomite	3774
sand	3836
lime	3863
Total Depth (KBM 5' above GL)	

TOPS:	SAMPLE	SCHLUMB.
Heebner		2300
Toronto		2317
Douglas sand		2338
Brown lime		2490
Lansing-KC	2546	2546
Mississippi	3188	3188
Kinderhook		3487
Maquoketa		3717
Viola		3736
Simpson	3774	3768
Arbuckle	3836	3836