


7-83W MAP NO. K-50 SEC. 5-20S-39W
 STATE Kans COUNTY Greeley LOC C SE SE
 OPER. Helmerich & Payne - Garden City, Kansas FT/FR _____ LINE _____
 WELL 1 FARM Angell FT/FR _____ LINE _____
 COL Geo WC - Unnamed Winf Gas Area _____ GR. _____ DF _____ KB _____
 ELEV. _____
 CONT. Sierra Pet Drlg. GEOL. Charles Nelson
 CO. INT. 5375' Oil Test
 F.R. 6-5-63 SPUD 6-3-63 COMP. 7-9-63
 TD. 5382 FM. St Louis PBTD. _____



COMP. RECORD

D&A

13 3/8" @325 w/300 sx.

Data Inc.

(KB Spl)		(KB Log)	
Winf	2799	Winf	2797 + 732
Hb	3995	Hb	3993 - 464
Tor	4014	Tor	4012 - 483
Lans	4047	Lans	4042 - 513
BKc	4506	BKc	4501 - 972
Marm	4540	Marm	4536 -1007
RTD	4580	Chero	4692 -1163
		Morr sh	4964 -1435
DST #1 (Hugoton) 2801-22, Op 1 hr, R		(Cont)	

50' M, ISIP 174#/30", IFP 45#,
 FFP 48#, FSIP 218#/30" - RTD 5380,

Morr sd	4966-76	-1437
" "	4985-90	-1456
St Gen	5149	-1620
St Lou	5262	-1733
LTD	5382	-1853

Log
 DST #2 (Morr) 4956-5110 (Str Pkr)
 Op 1½ hrs, R 170' M, ISIP 679
 #/30", IFP 44#, FFP 66#, FSIP
 197#/30"

DST #3 (Miss) 5160-5382, Op 2 hrs, R 300' M, ISIP 1198#/30",
 IFP 110#, FFP 153#, FSIP 745#/30"

WLT #1 (Marm) 4596-98½, Op 1 hr, No Rec, SP 50#, FSIP 50#/10"
 WLT #2 (Lans) 4344-46½, Op 110", R 44,200 cc wtr, ISIP 1230#/10"
 SP 50#, FSIP 1230#/5"

WLT #3 (Lans) 4146-48½, Op 1 hr, No Rec-all press less than 50#
 D&A - COMPLETED (6-27-63)

CORRECTION (6-6-63) Was: Pool - Is: Geol WC in Unnamed Winf
 Gas Area

AMARILLO TOPS

3529 KB

Winfield 2796 (-733) tst 50' Mud

Heebner 3994 (-465)

Lansing 4042 (-513) WLT no rec

Marmaton 4540 (-1011) WLT no rec

Morrow 4964 (-14 35)

"S-2" 4966 (-1437) 5/10; tst Mud

"S-2" 4985 (-1456) 6/6; tst mud

"S-3" 5058 (-1529) 22/58 brkn; tst mud

"S-3" 5138 (-1609) 0/6

Ste. Gen 5148 (-1619) tst mud

St. Louis 5256 (-1727) tst mud

TD 5381 D & A