


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.

WESTERN KANS. O.R.  
Steinbach No. 1.

SEC. 22 T. 20 R. 6W  
SE NE SE

Total Depth. 3395'  
Comm. 8-25-37 Comp. 9-19-37  
Shot or Treated.  
Contractor. Hannum Drlg. Co.  
Issued. 11-6-37

County. Rice



CASING:  
12 1/2" 118'  
7" 3330'

Elevation. 1597

Production. Pot. 183 B.

Figures Indicate Bottom of Formations.

soil	25
sdv lime	40
red beds	75
shale shells	132
lime	185
red rock	245
shale shells	290
shale & lime	375
shale & lime shells	550
sdv lime	600
shale lime shells	770
shale	845
lime & shale	870
shale & shells	925
lime	945
shale & shells	1220
shale	1330
brkn lime	1400
sdv lime	1420
shale shells	1505
lime	1535
brkn lime	1620
shale	1635
brkn lime	2000
shale	2090
brkn lime	2200
shale	2225
brkn lime	2250
lime	2275
brkn lime & shale	2330
lime	2480
sdv lime	2520
lime	2600
sand	2633
sdv lime	2690
brkn lime & shale	2740
lime & slate	2800
lime	2860
lime & slate	2910
shale & lime shells	2940
shale & shells	2950
lime	3122
sand	3127
shale	3137
lime	3190
brkn lime & shale	3230
lime & shale	3254
lime	3310
V C shale	3329
chat	3395
Total Depth.	

3329  
1597  
-----  
1732