


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

WESTGATE-GREENLAND OIL CO.
Johnson No. 3.

SEC. 24 T. 20 R. 6W
CS $\frac{1}{2}$ NE SE

Total Depth. 3362'
Comm. 7-5-40 Comp. 8-11-40
Shot or Treated.
Contractor. C.C. Nelson Drlg. Co.
Issued. 9-21-40

County. Rice



CASING:
10" 146'
7" 3277'

Elevation. 1526

Production. Pot. 16.08 B.

Figures Indicate Bottom of Formations.

shale	70
red bed & shells	163
shale & shells	423
shale & shells	770
anhydrite - lime	845
anhydrite	970
shale & lime	1015
shale	1025
lime sdy	1151
lime	1241
shale & lime	1358
lime	1478
shale & lime	1725
shale & lime	1970
shale & lime	2196
lime	2363
lime	2512
shale & lime	2693
lime	2817
lime	3139
shale & lime	3247
shale	3285
chat	3288
chat-sh oil, light	3294
chat	3302
chat sft	3314
chat	3333
small shale break	3321-27
chat-sm shale break	3340
chat & lime	3345
chat-green shale-sm break	3349
chat-sh oil	3354
chat-green shale-sm break	3357
lime	3362
Total Depth.	