


W. C. MCBRIDE, INC.
 Hodge No. 1.

SEC. 25 T. 20 R. 6W
 NW SE SE NE
 590' fr EL 410' fr SL NE

County. Rice

Total Depth. 3328'
 Comm. 11-25-39 Comp. 12-30-39
 Shot or Treated.
 Contractor. E.K. Carey Drlg. Co.
 Issued. 2-3-40



CASING:
 13" 152'
 85/8" 3278'

Elevation. 1524

Production. Pot. 710 B.

Figures Indicate Bottom of Formations.

cellar	10	Swab test 386 BO 24 hrs
soil & sand	30	12-24-39
sand	55	
shale red	75	Chat 3274-3328
shale	152	
shale blue	375	
shale & shells	440	
lime	480	
shale & salt	750	
shale & lime	914	
shale	940	
shale & lime	1035	
lime	1500	
shale & lime	1534	
lime	1590	
shale	1866	
shale & lime	1988	
lime & shale, brkn	2093	
shale	2146	
lime	2495	
shale	2546	
shale & lime	2570	
lime brkn	2620	
shale & lime	2660	
shale	2705	
shale & lime	2717	
shale	2769	
lime	2940	
shale & lime	3038	
lime	3085	
3027' 11" = 3030' 6" SIM		
shale	3100	
lime	3119	
lime & shale, brkn	3130	
shale & lime	3160	
lime	3195	
shale & lime	3240	
shale	3247	
shale var. col.	3263	
conglomerate	3273	
chert	3276	
chat	3311	
sm sh oil & gas	3291	
inc. in oil	3298-3300	
inc. in oil	3307-11	
sh wtr	3311-16	
hole filled 750' w/oil 15 H.		
filled 250' more in 7 Hrs		
while drilling 3311-16		
chert	3325 $\frac{1}{2}$	
hole filled up 250' 1 hr		
from 3319-21 $\frac{1}{2}$		
hole filled up 225' in 50		
min. from 3321 $\frac{1}{2}$ -23 $\frac{1}{2}$		
chat	3328	
Total Depth.		