

W. C. MCBRIDE, INC.
Hodge No. 4.


SEC. 25
CNL SE NE

T.20

R.6W

Total Depth. 3359'6" PB 3348'
Comm. 4-30-40 Comp. 5-25-40
Shot or Treated. 30 Qts. 5-20-40 3324-39
Contractor. E.K. Carey Drlg. Co.
Issued. 6-29-40

County. Rice



Rotary 0-3294'6"
Cable 3294'6"-3359'6"

CASING:

13" 115'
8 5/8" 3294'6"

Elevation. 1525

Production. Pot. 130 B.

Figures Indicate Bottom of Formations.

shale	80
sand	90
red rock	120
shale & shells	785
shale	825
lime	865
shale	1025
lime	1050
shale & lime	1230
lime	1295
shale	1300
lime brkn	1580
shale & sdy shale	1640
shale	1664
shale & shells	1770
shale	2090
shale sticky	2120
lime brkn	2160
shale & lime	2190
lime	2327
lime & chert shells	2385
lime	2555
shale	2630
lime	2643
shale & lime	2710
shale	2758
shale & lime	2800
lime	3164
shale	3230
shale & lime	3258 1/2
chert	3262
shale	3283 1/2
chat variegated	3289
chert	3295
3294 equals 3295 SLM	
R.U.S.T. 3295	
chat	3348
shale green	3352
shale red	3357
lime	3359'6"
Total Depth.	

Plugged Back to 3348
Bailing 25 gals. oil & 1 gal
wtr per hr

sm sh oil 3309-15 1/2
sm inc in oil & sh wtr 3324 1/2-29 1/2
sm amt gas 3333 1/2-3342
Production before shot 12 BOPD
Production after 30 Qts. from
3324-39 Pot. 130 B.

Mississippi lime 3291-3348