


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

WESTGATE-GREENLAND OIL CO.
Hodge No. 3

SEC. 25 T. 20 R. 6 W.
CS $\frac{1}{2}$ SW NE

Total Depth. 3373
Comm. 3-24-42 Comp. 4-22-42
Shot or Treated.
Contractor. C.C. Nelson Drilling Co.
Issued. 5-16-42

County Rice.



CASING.

10 3/4" 140' cemented.
7" 3280'

Elevation. 1525

Production. DRY

Figures Indicate Bottom of Formations.

clay and sand	55
shale and shells	780
anhydrite	870
anhydrite & shale	908
shale & shells	1025
lime	1030
lime and shale	1120
sharp sdy lime	1165
shale and lime	1270
shale & broken lime	1353
lime	1375
shale	1390
shale & lime shells	1508
lime	1580
shale and lime	1654
shale & broken lime	1690
lime	1714
shale	1810
shale and lime	1950
shale and lime	2082
shale	2195
lime	2505
shale and lime	2522
sdv lime	2625
lime	2644
shale	2815
lime	2915
lime hard	2956
lime and shale	3034
lime	3180
shale and lime	3276
chat	3280
Cable tool	
red rock	3288
chat	3373
Total Depth.	