


WESTGATE-GREENLAND OIL CO.
Harder No. 1.

SEC.36 T.20 R. 6 W
CN $\frac{1}{2}$ NW SW

Total Depth. 3415' PB 3376'
Comm. 10-13-41 Comp. 11-20-41
Shot or Treated.
Contractor. Nelson Drlg. Co.
Issued. 12-6-41

County. Rice



CASING:
10" 152'
5 $\frac{1}{2}$ " 3331'

Elevation. 1543

Production. Pot. 45 B.

Figures Indicate Bottom of Formations.

shale sdy	55
shale & shells	540
salt	700
shale	795
shale & lime shells	1020
shale & sand	1200
sdv lime & shale	1325
shale & lime	1500
shale	1640
lime & shale	1800
shale & shells	2120
lime & shale	2265
lime	2540
shale	2570
lime sdy	2650
shale & lime	2850
lime	2930
shale & lime	2945
lime hrd	3005
lime	3072
shale & lime	3314
shale	3328
chat	3331
chat	3408
shale green	3413
lime Miss.	3415
Total Depth.	

Plgd back to 3376