

Plugging
STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

October 22, 1987

Kelso Casing Pulling
PO Box 347
Chase, Kansas 67524

Attn: Mr. Darrell Kelso

RE: Plugging the Fry J #4 (drilled
4-21-64) and the Fry J #5
(drilled 4-27-66), Rice County
Kansas.

Dear Darrell:

We want you to apply for State Plugging orders to plug the above mentioned wells.

Fry J #4 C NE NE, Sec. 22-T20S-R6W, Rice County Kansas. 8 5/8" casing is set at 164' with 75 sacks; 4 1/2" casing is set at 3303 1/2' with 100 sacks. Set permanent bridge plug at 3200'. Perforated 2 shots per foot 3048'-50'; 2994'-98', 2952'-54', and 2900'-04'. Acidized each zone separately with 500 gallons of 15% FE Acid. No commercial oil or gas in these Kansas City Zones. Hole filled up with water to 700' of surface. (Casing only in hole) PBTD is 3200'.

Fry J #5 C NW NW, Sec. 23-T20S-R6W, Rice County, Kansas. 8 5/8" casing is set at 170' with 75 sacks; 4 1/2" casing is set at 3310' with 50 sacks. T.D. is 3334'. Mississippi formation. Hole or parted casing 350'-480'. ~~Moved up and down~~ when we pulled tubing.

If you want to work something out for plugging these wells where you get the casing and we put the top plug in please let us know.

Very truly yours,

Richard L. Mead
Richard L Mead, President

RLM:skp

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1987

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

OCT 28 1987

CONSERVATION DIVISION
Wichita, Kansas