

32-20-7W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BENNETT & GOULD
Farm- Davis


No. 2

SEC. 32 T. 20 R. 7W
NE NE NE

Total Depth. 3331'
Comm. 10-13-56 Comp. 10-21-56
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 10-26-57

County Rice

KANSAS



Elevation. 1623. DF

Production. 35 BOPD

CASING:

8 5/8" 130' w/175 sx cem.
5 1/2" 3309' w/75 sx cem.

Figures indicate Bottom of Formations.

shale-shells	200
shale-red bed-shells	1000
Anhydrite-shale-shells	1300
shale-shells	1495
shale-lime	1695
shale-shells	1920
shale-lime	2340
sand-shale	2390
lime-shale	2460
lime-sand	2580
lime-sand-shale	2670
sand-lime	2895
No log	2975
lime	3105
No log	3145
lime	3190
lime-shale	3260
lime	3311 RTD
No record	3331
Total Depth	

Cable Tool Report:

Picked up a slight show of oil under shoe. Drilled to 3319' no increase. Deepened to 3331'; picked up quite a bit of gas and filled up 300' of oil in 24 hrs.

Fractured and completed on the pump for 35 bbls. OPD

TOPS:

Heebner	2690
Brown lime	2847
Lansing	2876
B/Kansas City	3212
Cherty Conglomerate	3306

TOPS: Scout

Toronto	2706
Marmaton chert	3281