

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

32-20-7W

Company- H.C. BENNETT
Farm- Davis

No. 3

SEC. 32 T. 20 R. 7W
SE NE NE

Total Depth. 3336'
Comm. 10-22-56 Comp. 10-29-56
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 10-26-57

County Rice
KANSAS



CASING:

8 5/8" 200' w/165 sx cem.
5 1/2" 3319' w/75 sx cem.

Elevation. 1625 KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

sand-red bed-shells	200
red bed-shale-shells	960
shale-shells	1480
shale-lime	1885
shale-shells	2110
shale-lime	2440
lime	2645
lime-sand	2835
lime	3185
No log	3322 RTD
No log	3336
Total Depth	

Cable Tool drilled the plug,
picked up slight show @ 3319'.
Drilled to 3325', gas increased,
had fill up of 200' of fluid
over night mostly oil.
Drilled to a total Depth of 3336',
filled up over night w/800' fluid
75% oil.
Fractured and completed for 25 BOPD

TOPS:

Heebner	2690
Toronto	2709
Douglas	2714
Brown lime	2849
Lansing	2873
B/Kansas City	3215
Shaly Conglomerate	3306
Cherty Conglomerate	3312