

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg., Wichita, Kansas.


Plotted

SINCLAIR PRAIRIE OIL CO.
Chas. O. Sharpe No. 5.

7-20-9W
SEC. 7 T. 20 R. 9W
NE c NE
330' fr N & EL
N $\frac{1}{2}$ NE $\frac{1}{4}$

Total Depth. 3262 $\frac{1}{2}$ '
Comm. 4-16-36. Comp. 5-8-36
Shot or Treated. 1000 gals. Acid.
Contractor.
Issued. 7-11-36

County. Rice. *III* 11 1936



Casing:
12 $\frac{1}{2}$ " 163'
7 " 3241'
2 $\frac{1}{2}$ " tubing.

Elevation.

Production. Pot. 406

Figures Indicate Bottom of Formations. Oil, 100 wtr.

surface	20
shale & clay	156
shale & lime	164
shale & shells	775
shale & salt	1200
shale & shells	1275
shale & lime	1377
shale & shells	1548
shale & lime	1975
shale	2010
shale & lime	2060
shale	2125
shale & shells	2170
lime	2190
shale	2255
lime broken	2330
lime & shale	2400
lime	2447
broken lime	2507
lime	2673
lime hard	2750
lime & shale	2760
lime	2808
shale & lime	2940
Kansas City lime	2988
lime	3050
shale & lime	3246
Top Arbuckle	3242
lime arbuckle	3262 $\frac{1}{2}$
Total Depth	

Potential Production 406 B. Oil, 100 water after
1000 Gals. Acid.