

## KANSAS DRILLERS LOG

API No. 15 — 159 — 20731  
County Number

Operator

Aladdin Petroleum Corporation

Address

809 Petroleum Building, Wichita, Kansas 67202

Well No.

1

Lease Name

Hospital

AP-1

Footage Location

660

feet from (X) (S) line

660

feet from (E) (X) line of NW/4

Principal Contractor

B &amp; N Drilling

Geologist

Frank Marshall

Spud Date

1/27/78

Total Depth

1400

P.B.T.D.

Date Completed

4/10/78

Oil Purchaser


S. 1 T. 20 R. 8W X W

Loc. C SE NW

County Rice

640 Acres

N



Locate well correctly

Elev.: Gr. 1740

DF KB

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9-7/8"	7"	24#	208	Posmix	175	
Production	6-1/4"	4-1/2"	9-1/2#	1398	Posmix	75	

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	SDJ	1211-37
TUBING RECORD					
Size	Setting depth	Packer set at			

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2000 gals. 15% acid & 20 gals. detergent	1211-37

## INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	138 MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Aladdin Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Hospital	Gas
S 1 T 20S R 8W <del>W</del>		

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
top soil	0	10	Hollenberg	1168
shale/lime	10	43	Her. Krider	1204
sand	43	52	Winfield	1251 1261
lime	52	66	Towanda	1329
sand	66	153	Ft. Riley	1365
lime	153	1069		
shale/lime streaks	1069	1359		

Electric Log  
Welex - Radioactivity

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature 
	Title Geologist
	Date 4-14-78