


11-20-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DRILLERS PRODUCTION CO., INC & THOS. H. SEC. 11 T. 20 R. 8W
Farm- Sangster No. 1 ALLAN SE NE SW
990' SNL & 50' WEL of SW/4

Total Depth. 3197'
Comm. 10-23-54 Comp. 11-9-54
Shot or Treated.
Contractor. Thos. H. Allan
Issued. 2-19-55

County Rice KANSAS



CASING:
8 5/8" 170' cem w/140 sx
5 1/2" 3195' cem w/75 sx

Elevation. 1661' KB

Production. 3,310,000 Gas

Figures Indicate Bottom of Formations.

surface soil	30
sand & gravel	80
red beds & shale	482
shale & lime shells	740
salt & shale	980
shale & shells	1030
shale & lime	1335
shale	1355
lime	1535
shale & lime shells	1650
lime broken	1810
shale & lime	2235
lime & shale	2360
lime broken	2636
shale black	2641
lime	2651
shale gray & black	2661
lime	2672
shale	2680
lime	2687
sdv shale	2692
sand	2701
shale	2703
sand	2714
shale	2770
lime, some shale	2786
shale	2805
lime	3104
porous, no show	2852-56'
porous, no show	2900-09'
porous, SSO	2989-92'
porous, SSO	2999-3003'
porous, no show	3020-24'
shale	3113
lime	3119
shale varicolored	3148
chat & varicolored shale	3158
sand sl odor	3163
shale green	3187
Sst. sl show oil	3190
shale green	3193
dolomite	3197

Tops:	
Douglas	2687
Brown Lime	2770
Lansing	2805
Base Kansas City	3104
Cherty Conglomerate Sooy	3148
Simpson	3158
Arbuckle	3193

DST: 3115-75, open 1 hr, Rec 65' mud, SIP 20"
235#.

Drill in with 2" tubing & rotary Clean
out to TD & swab tubing. Acidize with 500 gal.

Poa