

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

MITCHELL DRILG CO.-SHELL OIL CO., INC.
G.L. Ginter No. 1.

SEC. 11 T. 20 R. 8W.
CWL SE SE
660' SL 990' EL SE $\frac{1}{2}$

Total Depth. 3312 P.B. 3265
Comm. 3-17-40 Comp. 5-22-40
Shot or Treated.
Contractor. Mitchell Drilg. Co.
Issued. 6-8-40

County Rice.

CASING.

85/8" 151'
5 1/2" 3295'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface and gravel	60
gravel	90
red bed	154
red bed and shale	355
shale soft blue	665
shale	965
shale and lime	1135
shale	1170
broken lime	1410
broken lime	1460
red bed and shale	1535
broken lime	1785
shale	2035
lime	2070
broken lime	2198
shale and lime	2296
lime	2495
broken lime	2535
lime	2670
shale	2693
lime soft	2735
shale	2815
lime	3095
lime	3181
shale and lime	3204
shale	3241
lime	3264
sdv lime	3290
sdv lime	3300

sand slightly oil
stained 3304
lime No saturation 3308

sand 3312
Total Depth.. P.B. 3265.

slight show oil and gas.
Swabbed water down, found no increase
in oil or gas as result of
acid treatment.
show water 3309. Increase of water from
3309-12. Bailed 10 bailers of water
per hour, could not deplete water.

Coring at 3296.
Cored from 3290-3300 Rec. 6 ft. blk shale and
3 ft sdv lime with green shale streaks.

Top of Simpson sand 3297.



El. 1655

No