

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Hurdock Wichita, Kansas

Company - ALLAN & BROOKS
Farm - Blevins

No. 1

SEC. 14 T. 20 R. 8W
NW NE SE

Total Depth. 3363 PB 3316
Comm. 1-14-50 Comp. 2-5-50
Shot or Treated.
Contractor. Tom Allan
Issued. 9-23-50

County. Rice
KANSAS



CASING:
8 5/8" 157' cem w/135 sx.
5 1/2" 3337' cem w/100 sx.

Elevation. 1644 DE

Production. Pot. 49 B0

Figures Indicate Bottom of Formations.

soil, sand, gravel	65	Tops:	
red beds	166	Anhydrite	166
anhydrite	178	Lansing	2839
red beds	500	Conglomerate	3207
shale	750	Misener	3335
salt, shale	1000	Maquoketa	3346
anhydrite	1100	Viola	3361
shale, shells	2350		
lime, shale partings	2700		
shale	3809	Swabbed salt water from	
lime brown	2813	Misener Sand.	
shale	2824	Lane-Wells plug top 3316	
sand	2829	One sack cement to top of	
shale	2839	plug.	
lime	2852	Perf. 3228-40 - 48 holes	
shale	2860	1000' oil in 4 hours.	
lime	2866		
shale	2870		
lime soft oolitic	2874		
lime	2887		
shale	2895		
lime	2901		
shale	2911		
lime	2924		
shale	2928		
lime	2941		
shale	2946		
lime soft oolitic	2958		
shale	2968		
lime	2988		
shale	2993		
lime	3010		
lime soft oolitic	3015		
lime	3033		
shale	3040		
lime soft oolitic	3055		
shale, lime	3080		
lime soft oolitic	3083		
lime	3105		
shale	3120		
lime cherty	3140		
shale	3155		
lime	3160		
shale, lime	3207		
red shale, congl.	3228		
chert varicolor (py)	3237-		
red shale	3265		
lime, shale	3280		
shale red, gray	3335		
sandstone wtr	3346		
dolomite	3361		
lime white xlyn	3363		
Total Depth			
Plugged back	3316		