

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - ALLAN & BROOKS
Farm - Williams No. 2

SEC. 14 T. 20 R. 8W
SW SW NE

Total Depth. 3326
Comm. 12-18-49 Comp. 1-11-50
Shot or Treated.
Contractor. Tom Allan
Issued. 4-22-50

County. Rice
KANSAS



8 5/8" CASING: 170' cem w/130 sx
5 1/2" 3320'

Elevation. _____

Pumped
Production. 60 Bbls.

Figures Indicate Bottom of Formations.

soil, sand & gravel	65
red beds	166
anhydrite	178
red beds	500
shale	750
salt & shale	1000
anhydrite	1150
shale & shells	1800
shale	2000
shale & shells	2375
lime & shale partings	2700
shale & sandy shale	2808
brown lime	2813
shale	2822
sand	2830
shale-	2840
lime	2860
shale	2866
soft oolitic lime	2870
lime	2883
shale	2890
soft oolitic lime	2896
shale & lime streaks	2910
lime & shale partings	2944
soft oolitic lime	2952
lime	2982
shale	3000
lime	3010
shale	3015
lime	3050
shale & lime streaks	3072
soft oolitic lime	3076
lime	3090
shale & lime streaks	3112
cherty lime	3120
lime & shale partings	3150
shale	3205
red conglomerate shale	3221
varicolor chert	3231
red mud	3238
varicolor chert	3240
red mud & some chert	3260
shale	3318
sandstone	3326
Total Depth	

Tops:

Anhydrite	166
Lansing	2840
Shale Conglomerate	3205
Lisener	3318

3326 T. D. sandstone oil stained.
Swabbed 2 bbl. oil & 3 bbl. water
per hour through 2 1/2" tubing.