

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East ~~Murdock~~, Wichita, Kansas


Company - HUTCHINS BROS.
Farm - Hutchins No. 1

SEC. 22 T. 20 R. 8W
NW SW SE

Total Depth. 3443½ P.B. 3400
Comm. 9-2-50 Comp. 9-21-50
Shot or Treated. Shot
Contractor. Tom Allan
Issued. 10-14-50

County. Rice

KANSAS



Elevation. 1653 RB

CASING:
8 5/8" 189' cem w/150 sz.
5 1/2" 3438' cem w/100 sz. P. 2736'

Production. dry

Depth from Rotary Bushings. Figures Indicate Bottom of Formations.

surface soil	20	Tops:	
gravel	85		
red beds	188	Anhydrite	188
anhydrite	200	Iatan	2869
red beds	520	Lansing	2899
shale	770	Sooy	3308
salt, shale	1020	Misener Sand	3437
anhydrite, shale	1220		
lime, shale	1420	Remarks:	
shale, shells	2520	3437-40	27 gal w/hr &
lime, shale brks	2720		tr. live oil
shale sandy	2790	3437-43½	164 gal w/hr &
shale	2869		tr live oil
lime	2877		Plug back to 3400
shale	2887		Perf: 3307-10 w/48 cone
sand	2891		shots.
shale	2899		Filled up 165' of water
lime	2907		in 1 hr. 15 min., with
lime, shale breaks	2925		tr. dead oil.
lime	2939		
shale	2944		
lime	2962		
lime, shale	2976		
lime, shale brks	3002		
lime	3043		
shale	3048		
lime, soft	3075		
shale	3080		
lime	3095		
lime, shale	3102		
lime, White Ool	3126		
lime, shale	3149		
lime	3155		
shale w/lime shells	3182		
lime, white ool	3185		
shale	3198		
lime	3202		
shale w/lime shells	3218		
lime	3228		
shale	3233		
lime	3237		
shale	3253		
lime	3257		
shale	3265		
lime, shale	3277		
shale; red, gray, green			
w/orange chert	3280		
shale, red, gray	3296		
shale, purple, chert	3300		
shale red, & mud	3308		
chert vari-colored	3313		
shale, red & gray	3347		
shale w/dolo. strks	3355		
lime, buff dense	3418		
shale	3437		
SL Corr Rotary	3440 RB =		
3437½ DF cable			
sand	3443½		
Total Depth			
Plugged back to	3400		