

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **ALLAN et al**

SEC. 27 T. 20 R. 8W

FARM **Will Edgar**

NO. **1**

LOC. **NE SE SW**

TOTAL DEPTH **3315**

COMM. **4-25-51**


SHOT OR TREATED

CONTRACTOR **Tom Allan**

ISSUED **6-16-51**

COMP. **5-15-51**

COUNTY **Rice**
KANSAS



CASINO

8 5/8" 205' cem. w/175 sx

5 1/2" 3303' cem. w/75 sx

ELEVATION **1661 RB**

swab

PRODUCTION **16 BOPD**

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil	35	Lansing	2905
sand & gravel	120	Cherty Conglomerate	3302
red beds	203		
anhydrite	245	Testing;	
red & green shale	340	Good show oil 3306-11	
shale gry & anhy.	370	Shot 14 Open Hole Koneshots	
red & green shale	500	(No Help)	
shale gry	760	Swab 16 BOPD	
red shale	790		
shale gry & salt	1020	Rotary Bushing Measurements	
anhydrite	1220		
lime	1310		
shale	1340		
cherty lime	1390		
shale	1440		
lime & shale	1520		
shale	1570		
lime	1650		
shale & shells	1890		
shale	2010		
shale & lime	2025		
shale	2090		
lime	2120		
sand & shale	2140		
shale & shells	2170		
shale	2240		
shale & shells	2410		
sand	2420		
shale & shells	2480		
lime	2565		
shale	2585		
lime	2670		
shale	2690		
lime & shale	2750		
sand & shale	2805		
shale & shells	2885		
shale & sand	2905		
lime & shale	3270		
red & green shale & orange chert	3300		
mud red & varicolored chert	3304		
Rotary 3304 = Cable Tools	3302		
sandy shale red & green	3306		
varicolored chert	3311		
shale red, green & gry	3315		
Total Depth			
Tops:			
Anhydrite	204		
Brown Lime	2877		