

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALLAN & BEREN
Farm- Thompson No. 1

SEC. 34 T. 20 R. 8W
SW SE NW

Total Depth. 3329

County Rice

Comm. 10-19-55

Comp. 11-4-55

KANSAS

Shot or Treated. Water-Frac: 3500# sand 277 BW-2200-2000 Press.

Contractor. Thomas H. Allan

Issued. 12-10-55



CASING:

8 5/8 @ 192' w/ 130 sx cmt.

Elevation. 1660 RB

5 1/2 @ 3313' w/ 75 sx cmt. 2752' pulled

Production. Dry

Figures Indicate Bottom of Formations.

soil	20
sand & gravel	90
yellow clay	130
red bed	187
anhydrite	192
red bed	500
shale	700
salt & shale	1000
anhydrite	1100
shale	1300
lime	1550
shale & shells	2400
lime	2750
shale	2880
brown lime	2886
shale & sand	2910
lime	2940
oolicastic lime	2946
lime	3016
oolicastic lime	3021
lime	3030
shale	3045
lime	3065
shale	3075
lime	3108
oolicastic lime	3117
lime	3195
lime & shale breaks	3231
shale	3240
lime	3252
shale	3260
red lime	3264
orange & amber chert	3266
red & green shale	3301
colored chert	3303
red & green shale	3310
vari-colored chert gravel RTD	3313
vari colored chert gravel	3319
red & green shale	3329
Total Depth	

TOPS:

Anhydrite	187
Brown lime	2880
Lansing	2910
Sooy conglomerate	3310
Kinderhook	3319

Tested 40 hrs./ 1 gal dead oil,
12 GFWPH

All RB Meas.