

29-20-9W


Company-M & L OIL CO.  
 Farm- Caldwell No. 1

SEC. 29 T. 20 R. 9W  
 NW NW NE

Total Depth. 3380  
 Comm. 4-26-53 Comp. 5-9-53  
 Shot or Treated.  
 Contractor. Bud Edwards Drilling Co.  
 Issued. 12-26-53

County Rice

KANSAS



Elevation. 1758 KB

Production. Dry

CASING:

8 5/8 @ 248' w/ 175 sx cmt.

Figures Indicate Bottom of Formations.

shale	35
sand	45
clay	80
sand	105
clay	190
shell	248
shale & shells w/ red rock	370
anhydrite	385
shale & shells	900
salt	1205
lime	1270
sand	1295
lime	1440
lime w/ sandy streaks	1600
lime	1940
lime w/ shale	2130
shale	2205
lime	2245
sandy shale	2248
sand	2260
lime w/ shale streaks	2480
shale	2555
lime	2865
shale w/ lime streaks	3005
lime	3305
Simpson sand	3310
shale w/ sand	3311
sand w/ shale	3321
shale ( inc red shale)	3322
sandy shale	3345
Arbuckle lime	3355
lime	3380
Total Depth	

TOPS:

Anhydrite ( d. l.)	370
Salt (d. l.)	900
Indian Cave	2239
Heebner	2827
Brown lime	2950
Lansing K C	2976
Simpson formation	3305
Arbuckle dolomite	3345

DST #1: 2250-60, open 1 hr. fair  
 blow, rec. 11' WCM 30' SW BHP 550# 20 min.

K B Measurements