

15-159-21056

20-20-9W

RECEIVED

FEB 03 2004

KCC WICHITA



RECEIVED

FEB 03 2004

KCC WICHITA

DRILL STEM TESTING AMARADA RECORDERS

P. O. BOX 1424

GREAT BEND, KANSAS

DRILL STEM TEST REPORT

LEASE Flanagan WELL NO. 1

Telephone
(316) 793-6347

Mobil — (316) 793-7859
Unit 7076



P. O. Box 1424
GREAT BEND, KANSAS 67530

RECEIVED

FEB 03 2004

KCC WICHITA

Company A. SCOTT RITCHIE Date 12-2-80

Address 125 N. MAKRET - SUITE 950 WICHITA, KANSAS 67202

Drilling Contractor WOODMAN-IANNITTI Rig No. 2

Lease, Well No. FLANAGAN # 1 County RICE Sec. 20 Twp. 20S Rng. 9W

Size Hole 7 7/8 Size Pipe 4 1/2 X.H. Size Tool 3 1/2 F.H.

Size Packer 6 3/4 x 2 7/8 x 30 Size Choke 5/8 Size Anchor 4 1/2 F.H.

Interval Tested 3083 to 3092 Total Depth 3092

Test No. 1 Successful No. 1 Misrun No. 0

Formation Tested KC Time Packer Set 12:50 A.M. Time Tool Opened 12:55 A.M.

Tool Open 30-30 Min. Initial Shut-in-Time 30 Min. Final Shut-in-Time 30 Min.

Blow VERY WEAK BLOW ON FIRST OPENING, DIED IN 18 MINUTES.

VERY WEAK BLOW ON SECOND OPENING, DIED IN 18 MINUTES.

Recovery 10 FEET OF THIN DRILLING MUD.

Remarks: TEMPERATURE 100 DEGREES.

Initial BHP 394 IFP 32-32 FFP 32-21 Final BHP 74

Hydrastatic Press. 1703-1671 Mud Wt. 9.9 Vis. 45 Water Loss 8

Extra Equipment _____ Jars _____ Straddle Packer _____ Safety Joint _____

Tester TOM BRANAN Approved By ROGER FISCHER Ticket No. 264

